



## TYPICAL INSTALLATION- 2" SERVICE STEEL MAIN

## NOTES:

- 1 FRONT OF METER BOX TO BE LOCATED 6" BEHIND BACK OF WALK FOR SIDEWALK ADJACENT TO CURB AND 4" BACK OF CURB FOR SIDEWALK ADJACENT TO RIGHT OF WAY, UNLESS OTHERWISE SPECIFIED.
- 2 RUN COPPER, TYPE "K", SERVICE TO PROPERTY LINE OR AS REQUIRED METER SIZE X 12" LONG BRASS NIPPLE.
- 3 METER (1 1/2" OR 2") SHALL BE SUPPLIED BY THE CITY AT CONTRACTOR'S EXPENSE, UNLESS OTHERWISE APPROVED.
- 4 2" COPPER TUBING, TYPE "K", FROM CORP. STOP TO ANGLE METER STOP (ONE CONTINUOUS PIECE OF PIPE). SLEEVE TUBING REQUIRED IN CORROSIVE SOIL AREAS.



APPROVED BY:

LOUIS ABI-YOUNES, CITY ENGINEER RCE DATE

RECOMMENDED:

DENNIS MEJIA, UTILITIES ENGINEERING DIRECTOR RCE DATE

REV DESCRIPTION BY APP'D DATE

CITY OF ONTARIO

2" WATER SERVICE

STANDARD DRAWING NUMBER

4202